

HULL TRUCK THEATRE

STRUCTURAL WORKS



Date awarded

March 2007

Duration

34 weeks

Contract Value

£2m

Gibson Lane, Melton, North Ferriby,
East Yorkshire, HU14 3HH, England

Tel: 01482 637373

Fax: 01482 637370

Email: info@crreynolds.co.uk

C.R.Reynolds
(CONSTRUCTION) LTD



Description of Work

The works were to construct a 5 storey reinforced concrete structure within an extremely restricted city centre development.

The works initially comprised dewatering to allow basement construction to be carried out and the installation of a 50m tower crane.

The structure consisted of approximately 4000m² of RC walls & beams which were constructed using traditional formwork and 2500m² of RC deck which was constructed using a bespoke formwork decking system lined with laminated plywood to create a brick-bond patterned concrete finish.

All concrete finishes are exposed to create an industrial feel and therefore construction was completed to an extremely high specification.